



KANCHRAPARA COLLEGE

Kanchrapara, North 24-Parganas
Pin – 743 145

Ph. No. 2585 8790
2585 5159

E-mail – info@kpcoll.ac.in

ESTD – 1972

website: <http://www.kanchraparacollege.ac.in>

Ref. No.: KPC/PC/IQAC/WARDROBE/-001

Date: 05/09/2024

Notice Inviting Tender Quotation

Sealed Quotations are invited from the reputed bonafide Contractor/ Supplier for Different type of Improvement / Different kind of work / Lease under KanchraparaCollege Having sufficient credential and financial like (GST Certificate, PAN, P.Tax (Challan)(2020-21) & Income tax return for Last Year updated and Similar Nature of work done completion certificate of value at least 40% of the estimated amount of the respective work in a single contract within last 3 years with is applicable for eligibility in this tender)capability for execution of works as depicted hereunder for participating in the tender.

Sl. No	Name of the work	Estimated amount put to tender WITH GST AND Contingency (inRs.)	Earnest Money 2% of Estimate Amount (inRs.)	Cost of Tender Documents (Applicable for the successful Contractor only at the time of formal agreement) (inRs.)
1	SUPPLY, FITTING & FIXING WARDROPE IQAC ROOM (ZONE A & B)	86726/-	NIL	

Last date of submission of Tender/quotation paper	14.09.2024
Place of receipt of Quotation	Tender Box, Front of Principal Chamber
Time and date of opening of Quotation	16.09.2024, 3P.M.
Place of opening of Quotation	Principal Chamber

1. Tenderers shall ensure that their tenders duly sealed and signed, complete in all respects as per instructions contained in the Quotation Documents, are dropped in the tender box located at the address given bellow on or before the closing date and time indicated in the table above. Falling which the tenders will be treated as late and reject.
2. In the event of any of the above mentioned dates being declared as a holiday/closed day for the purchase organization, the tenders will be sold/received/opened on the next working day at the appointed time.
3. The quotation documents are not transferable.
4. The undersigned has received the right to accept or reject the tender without any reason whatsoever.

Principal
Kanchrapara College
Kanchrapara, 24 Pgs.(N)



KANCHRAPARA COLLEGE

Kanchrapara, North 24-Parganas
Pin – 743 145

Ph. No. 2585 8790
2585 5159

E-mail – info@kpcoll.ac.in

ESTD – 1972

website: <http://www.kanchraparacollege.ac.in>

Ref. No.: KPC/PC/DC/Painting/-002

Date: 05/09/2024

Notice Inviting Tender Quotation

Sealed Quotations are invited from the reputed bonafide Contractor/ Supplier for Different type of Improvement / Different kind of work / Lease under KanchraparaCollege Having sufficient credential and financial like (GST Certificate, PAN, P.Tax (Challan)(2020-21) & Income tax return for Last Year updated and Similar Nature Of work done completion certificate of value at least 40% of the estimated amount of the respective work in a single contract within last 3 years with is applicable for eligibility in this tender)capability for execution of works as depicted hereunder for participating in the tender.

Sl. No	Name of the work	Estimated amount put to tender WITH GST AND Contingency (inRs.)	Earnest Money 2% of Estimate Amount (inRs.)	Cost of Tender Documents (Applicable for the successful Contractor only at the time of formal agreement) (inRs.)
1	PAINTING WITH PUTTY, TILES DOCTOR ROOM	35024/-	NIL	

Last date of submission of Tender/quotation paper	14.09.2024
Place of receipt of Quotation	Tender Box, Front of Principal Chamber
Time and date of opening of Quotation	16.09.2024, 3P.M.
Place of opening of Quotation	Principal Chamber

1. Tenderers shall ensure that their tenders duly sealed and signed, complete in all respects as per instructions contained in the Quotation Documents, are dropped in the tender box located at the address given bellow on or before the closing date and time indicated in the table above. Falling which the tenders will be treated as late and reject.
2. In the event of any of the above mentioned dates being declared as a holiday/closed day for the purchase organization, the tenders will be sold/received/opened on the next working day at the appointed time.
3. The quotation documents are not transferable.
4. The undersigned has received the right to accept or reject the tender without any reason whatsoever.

Principal
Kanchrapara College
Kanchrapara, 24 Pgs.(N)



KANCHRAPARA COLLEGE

Kanchrapara, North 24-Parganas
Pin – 743 145

Ph. No. 2585 8790
2585 5159

E-mail – info@kpcoll.ac.in

ESTD – 1972

website: <http://www.kanchraparacollege.ac.in>

Ref. No: KPC/IQAC/Bathroom/Painting & Sanitary Fittings/-003

Date: 05/09/2024

Notice Inviting Tender Quotation

Sealed Quotations are invited from the reputed bonafide Contractor/ Supplier for Different type of Improvement / Different kind of work / Lease under KanchraparaCollege Having sufficient credential and financial like (GST Certificate, PAN, P.Tax (Challan)(2020-21) & Income tax return for Last Year updated and Similar Nature of work done completion certificate of value at least 40% of the estimated amount of the respective work in a single contract within last 3 years with is applicable for eligibility in this tender)capability for execution of works as depicted hereunder for participating in the tender.

Sl. No	Name of the work	Estimated amount put to tender WITH GST AND Contingency (inRs.)	Earnest Money 2% of Estimate Amount (inRs.)	Cost of Tender Documents (Applicable for the successful Contractor only at the time of formal agreement) (inRs.)
1	PAINTING & SANITARY FITTINGS AT IQAC BTHROOM (ZONE A & B)	99407/-	NIL	

Last date of submission of Tender/quotation paper	14.09.2024
Place of receipt of Quotation	Tender Box, Front of Principal Chamber
Time and date of opening of Quotation	16.09.2024, 3P.M.
Place of opening of Quotation	Principal Chamber

1. Tenderers shall ensure that their tenders duly sealed and signed, complete in all respects as per instructions contained in the Quotation Documents, are dropped in the tender box located at the address given bellow on or before the closing date and time indicated in the table above. Falling which the tenders will be treated as late and reject.
2. In the event of any of the above mentioned dates being declared as a holiday/closed day for the purchase organization, the tenders will be sold/received/opened on the next working day at the appointed time.
3. The quotation documents are not transferable.
4. The undersigned has received the right to accept or reject the tender without any reason whatsoever.

Principal
Kanchrapara College
Kanchrapara, 24 Pgs.(N)



KANCHRAPARA COLLEGE
Kanchrapara, North 24-Parganas
Pin – 743 145

Ph. No. 2585 8790
2585 5159

E-mail – info@kpcoll.ac.in

ESTD – 1972

website: <http://www.kanchraparacollege.ac.in>

Ref. No.: KPC/IQAC/Bathroom/Painting, Tiles & False Ceiling Fittings/-004

Date: 05/09/2024

Notice Inviting Tender Quotation

Sealed Quotations are invited from the reputed bonafide Contractor/ Supplier for Different type of Improvement / Different kind of work / Lease under KanchraparaCollege Having sufficient credential and financial like (GST Certificate, PAN, P.Tax (Challan)(2020-21) & Income tax return for Last Year updated and Similar Nature Of work done completion certificate of value at least 40% of the estimated amount of the respective work in a single contract within last 3 years with is applicable for eligibility in this tender)capability for execution of works as depicted hereunder for participating in the tender.

Sl. No	Name of the work	Estimated amount put to tender WITH GST AND Contingency (inRs.)	Earnest Money 2% of Estimate Amount (inRs.)	Cost of Tender Documents (Applicable for the successful Contractor only at the time of formal agreement) (inRs.)
1	PUTTY, FALSE CELING & TITLES WORK AT IQAC BATHROOM (ZONE A & B)	93961/-	NIL	

Last date of submission of Tender/quotation paper	14.09.2024
Place of receipt of Quotation	Tender Box, Front of Principal Chamber
Time and date of opening of Quotation	16.09.2024, 3P.M.
Place of opening of Quotation	Principal Chamber

1. Tenderers shall ensure that their tenders duly sealed and signed, complete in all respects as per instructions contained in the Quotation Documents, are dropped in the tender box located at the address given bellow on or before the closing date and time indicated in the table above. Falling which the tenders will be treated as late and reject.
2. In the event of any of the above mentioned dates being declared as a holiday/closed day for the purchase organization, the tenders will be sold/received/opened on the next working day at the appointed time.
3. The quotation documents are not transferable.
4. The undersigned has received the right to accept or reject the tender without any reason whatsoever.

Principal
Kanchrapara College
Kanchrapara, 24 Pgs.(N)



KANCHRAPARA COLLEGE
Kanchrapara, North 24-Parganas
Pin – 743 145

Ph. No. 2585 8790
2585 5159

E-mail – info@kpcoll.ac.in

ESTD – 1972

website: <http://www.kanchraparacollege.ac.in>

Ref. No.: KPC/NSS/ Painting With Putty /-005

Date: 05/09/2024

Notice Inviting Tender Quotation

Sealed Quotations are invited from the reputed bonafide Contractor/ Supplier for Different type of Improvement / Different kind of work / Lease under KanchraparaCollege Having sufficient credential and financial like (GST Certificate, PAN, P.Tax (Challan)(2020-21) & Income tax return for Last Year updated and Similar Nature Of work done completion certificate of value at least 40% of the estimated amount of the respective work in a single contract within last 3 years with is applicable for eligibility in this tender)capability for execution of works as depicted hereunder for participating in the tender.

Sl. No	Name of the work	Estimated amount put to tender WITH GST AND Contingency (inRs.)	Earnest Money 2% of Estimate Amount (inRs.)	Cost of Tender Documents (Applicable for the successful Contractor only at the time of formal agreement) (inRs.)
1	PAINTING WITH PUTTY NSS ROOM	79204/-	NIL	

Last date of submission of Tender/quotation paper	14.09.2024
Place of receipt of Quotation	Tender Box, Front of Principal Chamber
Time and date of opening of Quotation	16.09.2024, 3P.M.
Place of opening of Quotation	Principal Chamber

1. Tenderers shall ensure that their tenders duly sealed and signed, complete in all respects as per instructions contained in the Quotation Documents, are dropped in the tender box located at the address given bellow on or before the closing date and time indicated in the table above. Falling which the tenders will be treated as late and reject.
2. In the event of any of the above mentioned dates being declared as a holiday/closed day for the purchase organization, the tenders will be sold/received/opened on the next working day at the appointed time.
3. The quotation documents are not transferable.
4. The undersigned has received the right to accept or reject the tender without any reason whatsoever.

Principal
Kanchrapara College
Kanchrapara, 24 Pgs.(N)



KANCHRAPARA COLLEGE
Kanchrapara, North 24-Parganas
Pin – 743 145

Ph. No. 2585 8790
2585 5159

E-mail – info@kpcoll.ac.in

ESTD – 1972

website: <http://www.kanchraparacollege.ac.in>

Ref. No: KPC/IQAC/ Electric Lights & Wiring Fittings/-006

Date: 05/09/2024

Notice Inviting Tender Quotation

Sealed Quotations are invited from the reputed bonafide Contractor/ Supplier for Different type of Improvement / Different kind of work / Lease under KanchraparaCollege Having sufficient credential and financial like (GST Certificate, PAN, P.Tax (Challan)(2020-21) & Income tax return for Last Year updated and Similar Nature Of work done completion certificate of value at least 40% of the estimated amount of the respective work in a single contract within last 3 years with is applicable for eligibility in this tender)capability for execution of works as depicted hereunder for participating in the tender.

Sl. No.	Name of the work	Estimated amount put to tender WITH GST AND Contingency (inRs.)	Earnest Money 2% of Estimate Amount (inRs.)	Cost of Tender Documents (Applicable for the successful Contractor only at the time of formal agreement) (inRs.)
1	ELECTRIC LED LIGHT & WIRING AT IQAC ROOM (ZONE A & B)	51724/-	NIL	

Last date of submission of Tender/quotation paper	14.09.2024
Place of receipt of Quotation	Tender Box, Front of Principal Chamber
Time and date of opening of Quotation	16.09.2024, 3P.M.
Place of opening of Quotation	Principal Chamber

1. Tenderers shall ensure that their tenders duly sealed and signed, complete in all respects as per instructions contained in the Quotation Documents, are dropped in the tender box located at the address given bellow on or before the closing date and time indicated in the table above. Falling which the tenders will be treated as late and reject.
2. In the event of any of the above mentioned dates being declared as a holiday/closed day for the purchase organization, the tenders will be sold/received/opened on the next working day at the appointed time.
3. The quotation documents are not transferable.
4. The undersigned has received the right to accept or reject the tender without any reason whatsoever.

Principal
Kanchrapara College
Kanchrapara, 24 Pgs.(N)



KANCHRAPARA COLLEGE
Kanchrapara, North 24-Parganas
Pin – 743 145

Ph. No. 2585 8790
2585 5159

E-mail – info@kpcoll.ac.in

ESTD – 1972

website: <http://www.kanchraparacollege.ac.in>

Ref. No: KPC/IQAC/ Partition Wall & Door Frame (Zone B)/-007

Date: 05/09/2024

Notice Inviting Tender Quotation

Sealed Quotations are invited from the reputed bonafide Contractor/ Supplier for Different type of Improvement / Different kind of work / Lease under KanchraparaCollege Having sufficient credential and financial like (GST Certificate, PAN, P.Tax (Challan)(2020-21) & Income tax return for Last Year updated and Similar Nature Of work done completion certificate of value at least 40% of the estimated amount of the respective work in a single contract within last 3 years with is applicable for eligibility in this tender)capability for execution of works as depicted hereunder for participating in the tender.

Sl. No	Name of the work	Estimated amount put to tender WITH GST AND Contingency (inRs.)	Earnest Money 2% of Estimate Amount (inRs.)	Cost of Tender Documents (Applicable for the successful Contractor only at the time of formal agreement) (inRs.)
1	PARTION WALL WITH ACP SHEET FOR RENOVATION IQAC ROOM (ZONE B) & DOORS FRAMES	98852-	NIL	

Last date of submission of Tender/quotation paper	14.09.2024
Place of receipt of Quotation	Tender Box, Front of Principal Chamber
Time and date of opening of Quotation	16.09.2024, 3P.M.
Place of opening of Quotation	Principal Chamber

1. Tenderers shall ensure that their tenders duly sealed and signed, complete in all respects as per instructions contained in the Quotation Documents, are dropped in the tender box located at the address given bellow on or before the closing date and time indicated in the table above. Falling which the tenders will be treated as late and reject.
2. In the event of any of the above mentioned dates being declared as a holiday/closed day for the purchase organization, the tenders will be sold/received/opened on the next working day at the appointed time.
3. The quotation documents are not transferable.
4. The undersigned has received the right to accept or reject the tender without any reason whatsoever.

Principal
Kanchrapara College
Kanchrapara, 24 Pgs.(N)



KANCHRAPARA COLLEGE
Kanchrapara, North 24-Parganas
Pin – 743 145

Ph. No. 2585 8790
2585 5159

E-mail – info@kpcoll.ac.in

ESTD – 1972

website: <http://www.kanchraparacollege.ac.in>

Ref. No.: KPC/IQAC/ Partition Wall & Door Frame (Zone A)/-008

Date: 05/09/2024

Notice Inviting Tender Quotation

Sealed Quotations are invited from the reputed bonafide Contractor/ Supplier for Different type of Improvement / Different kind of work / Lease under KanchraparaCollege Having sufficient credential and financial like (GST Certificate, PAN, P.Tax (Challan)(2020-21) & Income tax return for Last Year updated and Similar Nature Of work done completion certificate of value at least 40% of the estimated amount of the respective work in a single contract within last 3 years with is applicable for eligibility in this tender)capability for execution of works as depicted hereunder for participating in the tender.

Sl. No	Name of the work	Estimated amount put to tender WITH GST AND Contingency (inRs.)	Earnest Money 2% of Estimate Amount (inRs.)	Cost of Tender Documents (Applicable for the successful Contractor only at the time of formal agreement) (inRs.)
1	PARTITION WALL WITH ACP SHEET FOR RENOVATION IQAC ROOM (ZONE A)	99813/-	NIL	

Last date of submission of Tender/quotation paper	14.09.2024
Place of receipt of Quotation	Tender Box, Front of Principal Chamber
Time and date of opening of Quotation	16.09.2024, 3P.M.
Place of opening of Quotation	Principal Chamber

1. Tenderers shall ensure that their tenders duly sealed and signed, complete in all respects as per instructions contained in the Quotation Documents, are dropped in the tender box located at the address given bellow on or before the closing date and time indicated in the table above. Falling which the tenders will be treated as late and reject.
2. In the event of any of the above mentioned dates being declared as a holiday/closed day for the purchase organization, the tenders will be sold/received/opened on the next working day at the appointed time.
3. The quotation documents are not transferable.
4. The undersigned has received the right to accept or reject the tender without any reason whatsoever.

Principal
Kanchrapara College
Kanchrapara, 24 Pgs.(N)



KANCHRAPARA COLLEGE
Kanchrapara, North 24-Parganas
Pin – 743 145

Ph. No. 2585 8790
2585 5159

E-mail – info@kpcoll.ac.in

ESTD – 1972

website: <http://www.kanchraparacollege.ac.in>

Ref. No.: KPC/IQAC/ False Ceiling & Calcium Silicate Board (Zone A&B)/-009

Date: 05/09/2024

Notice Inviting Tender Quotation

Sealed Quotations are invited from the reputed bonafide Contractor/ Supplier for Different type of Improvement / Different kind of work / Lease under KanchraparaCollege Having sufficient credential and financial like (GST Certificate, PAN, P.Tax (Challan)(2020-21) & Income tax return for Last Year updated and Similar Nature Of work done completion certificate of value at least 40% of the estimated amount of the respective work in a single contract within last 3 years with is applicable for eligibility in this tender)capability for execution of works as depicted hereunder for participating in the tender.

Sl. No.	Name of the work	Estimated amount put to tender WITH GST AND Contingency (inRs.)	Earnest Money 2% of Estimate Amount (inRs.)	Cost of Tender Documents (Applicable for the successful Contractor only at the time of formal agreement) (inRs.)
1	FALSE CELLING WITH G.I. GRID SUSI ENSION SYSTEM & CALCUM SILICATE BOARD FOR RENOVATION OF IQAC ROOM (ZONE A & B)	99849-	NIL	

Last date of submission of Tender/quotation paper	14.09.2024
Place of receipt of Quotation	Tender Box, Front of Principal Chamber
Time and date of opening of Quotation	16.09.2024, 3P.M.
Place of opening of Quotation	Principal Chamber

1. Tenderers shall ensure that their tenders duly sealed and signed, complete in all respects as per instructions contained in the Quotation Documents, are dropped in the tender box located at the address given bellow on or before the closing date and time indicated in the table above. Falling which the tenders will be treated as late and reject.
2. In the event of any of the above mentioned dates being declared as a holiday/closed day for the purchase organization, the tenders will be sold/received/opened on the next working day at the appointed time.
3. The quotation documents are not transferable.
4. The undersigned has received the right to accept or reject the tender without any reason whatsoever.

Principal
Kanchrapara College
Kanchrapara, 24 Pgs.(N)



KANCHRAPARA COLLEGE

Kanchrapara, North 24-Parganas
Pin – 743 145

Ph. No. 2585 8790
2585 5159

E-mail – info@kpcoll.ac.in

ESTD – 1972

website: <http://www.kanchraparacollege.ac.in>

Ref. No.: KPC/IQAC/Aluminum Alloy Section (Zone A&B)/-0010

Date: 05/09/2024

Notice Inviting Tender Quotation

Sealed Quotations are invited from the reputed bonafide Contractor/ Supplier for Different type of Improvement / Different kind of work / Lease under KanchraparaCollege Having sufficient credential and financial like (GST Certificate, PAN, P.Tax (Challan)(2020-21) & Income tax return for Last Year updated and Similar Nature Of work done completion certificate of value at least 40% of the estimated amount of the respective work in a single contract within last 3 years with is applicable for eligibility in this tender)capability for execution of works as depicted hereunder for participating in the tender.

Sl. No	Name of the work	Estimated amount put to tender WITH GST AND Contingency (inRs.)	Earnest Money 2% of Estimate Amount (inRs.)	Cost of Tender Documents (Applicable for the successful Contractor only at the time of formal agreement) (inRs.)
1	ALUMINIUM ALLOY SECTION FOR PARTITION WALL IQAC ROOM (ZONE A & B)	99276/-	NIL	

Last date of submission of Tender/quotation paper	14.09.2024
Place of receipt of Quotation	Tender Box, Front of Principal Chamber
Time and date of opening of Quotation	16.09.2024, 3P.M.
Place of opening of Quotation	Principal Chamber

1. Tenderers shall ensure that their tenders duly sealed and signed, complete in all respects as per instructions contained in the Quotation Documents, are dropped in the tender box located at the address given bellow on or before the closing date and time indicated in the table above. Falling which the tenders will be treated as late and reject.
2. In the event of any of the above mentioned dates being declared as a holiday/closed day for the purchase organization, the tenders will be sold/received/opened on the next working day at the appointed time.
3. The quotation documents are not transferable.
4. The undersigned has received the right to accept or reject the tender without any reason whatsoever.

Principal
Kanchrapara College
Kanchrapara, 24 Pgs.(N)



KANCHRAPARA COLLEGE
Kanchrapara, North 24-Parganas
Pin – 743 145

Ph. No. 2585 8790
2585 5159

E-mail – info@kpcoll.ac.in

ESTD – 1972

website: <http://www.kanchraparacollege.ac.in>

Ref. No.: KPC/IQAC/Painting & Putty Renovation (Zone A&B)/-0011

Date: 05/09/2024

Notice Inviting Tender Quotation

Sealed Quotations are invited from the reputed bonafide Contractor/ Supplier for Different type of Improvement / Different kind of work / Lease under KanchraparaCollege Having sufficient credential and financial like (GST Certificate, PAN, P.Tax (Challan)(2020-21) & Income tax return for Last Year updated and Similar Nature Of work done completion certificate of value at least 40% of the estimated amount of the respective work in a single contract within last 3 years with is applicable for eligibility in this tender)capability for execution of works as depicted hereunder for participating in the tender.

Sl. No	Name of the work	Estimated amount put to tender WITH GST AND Contingency (inRs.)	Earnest Money 2% of Estimate Amount (inRs.)	Cost of Tender Documents (Applicable for the successful Contractor only at the time of formal agreement) (inRs.)
1	PAINTING WITH PUTTY RENOVETION IQAC ROOM (ZONE A & B)	99727-	NIL	

Last date of submission of Tender/quotation paper	14.09.2024
Place of receipt of Quotation	Tender Box, Front of Principal Chamber
Time and date of opening of Quotation	16.09.2024, 3P.M.
Place of opening of Quotation	Principal Chamber

1. Tenderers shall ensure that their tenders duly sealed and signed, complete in all respects as per instructions contained in the Quotation Documents, are dropped in the tender box located at the address given bellow on or before the closing date and time indicated in the table above. Falling which the tenders will be treated as late and reject.
2. In the event of any of the above mentioned dates being declared as a holiday/closed day for the purchase organization, the tenders will be sold/received/opened on the next working day at the appointed time.
3. The quotation documents are not transferable.
4. The undersigned has received the right to accept or reject the tender without any reason whatsoever.

Principal
Kanchrapara College
Kanchrapara, 24 Pgs.(N)



KANCHRAPARA COLLEGE
Kanchrapara, North 24-Parganas
Pin – 743 145

Ph. No. 2585 8790
2585 5159

E-mail – info@kpcoll.ac.in

ESTD – 1972

website: <http://www.kanchraparacollege.ac.in>

Ref. No.: KPC/IQAC/Tiles work (Zone A&B)/-0012

Date: 05/09/2024

Notice Inviting Tender Quotation

Sealed Quotations are invited from the reputed bonafide Contractor/ Supplier for Different type of Improvement / Different kind of work / Lease under KanchraparaCollege Having sufficient credential and financial like (GST Certificate, PAN, P.Tax (Challan)(2020-21) & Income tax return for Last Year updated and Similar Nature Of work done completion certificate of value at least 40% of the estimated amount of the respective work in a single contract within last 3 years with is applicable for eligibility in this tender)capability for execution of works as depicted hereunder for participating in the tender.

Sl. No	Name of the work	Estimated amount put to tender WITH GST AND Contingency (inRs.)	Earnest Money 2% of Estimate Amount (inRs.)	Cost of Tender Documents (Applicable for the successful Contractor only at the time of formal agreement) (inRs.)
1	TILES WORK FOR FLOOR RENOVATION IQAC ROOM (ZONE A & B)	99917-	NIL	

Last date of submission of Tender/quotation paper	14.09.2024
Place of receipt of Quotation	Tender Box, Front of Principal Chamber
Time and date of opening of Quotation	16.09.2024, 3P.M.
Place of opening of Quotation	Principal Chamber

1. Tenderers shall ensure that their tenders duly sealed and signed, complete in all respects as per instructions contained in the Quotation Documents, are dropped in the tender box located at the address given bellow on or before the closing date and time indicated in the table above. Falling which the tenders will be treated as late and reject.
2. In the event of any of the above mentioned dates being declared as a holiday/closed day for the purchase organization, the tenders will be sold/received/opened on the next working day at the appointed time.
3. The quotation documents are not transferable.
4. The undersigned has received the right to accept or reject the tender without any reason whatsoever.

Principal
Kanchrapara College
Kanchrapara, 24 Pgs.(N)



KANCHRAPARA COLLEGE
Kanchrapara, North 24-Parganas
Pin – 743 145

Ph. No. 2585 8790
2585 5159

E-mail – info@kpcoll.ac.in

ESTD – 1972

website: <http://www.kanchraparacollege.ac.in>

Ref. No.: KPC/NSS/ Tiles Fittings /-0013

Date: 05/09/2024

Notice Inviting Tender Quotation

Sealed Quotations are invited from the reputed bonafide Contractor/ Supplier for Different type of Improvement / Different kind of work / Lease under KanchraparaCollege Having sufficient credential and financial like (GST Certificate, PAN, P.Tax (Challan)(2020-21) & Income tax return for Last Year updated and Similar Nature of work done completion certificate of value at least 40% of the estimated amount of the respective work in a single contract within last 3 years with is applicable for eligibility in this tender)capability for execution of works as depicted hereunder for participating in the tender.

Sl. No	Name of the work	Estimated amount put to tender WITH GST AND Contingency (inRs.)	Earnest Money 2% of Estimate Amount (inRs.)	Cost of Tender Documents (Applicable for the successful Contractor only at the time of formal agreement) (inRs.)
1	TILES Fittings AT NSS ROOM	99314/-	NIL	

Last date of submission of Tender/quotation paper	14.09.2024
Place of receipt of Quotation	Tender Box, Front of Principal Chamber
Time and date of opening of Quotation	16.09.2024, 3P.M.
Place of opening of Quotation	Principal Chamber

1. Tenderers shall ensure that their tenders duly sealed and signed, complete in all respects as per instructions contained in the Quotation Documents, are dropped in the tender box located at the address given bellow on or before the closing date and time indicated in the table above. Falling which the tenders will be treated as late and reject.
2. In the event of any of the above mentioned dates being declared as a holiday/closed day for the purchase organization, the tenders will be sold/received/opened on the next working day at the appointed time.
3. The quotation documents are not transferable.
4. The undersigned has received the right to accept or reject the tender without any reason whatsoever.

Principal
Kanchrapara College
Kanchrapara, 24 Pgs.(N)

Estimate No.01/KPA/24-25

ESTIMATE FOR TILES WORK FOR FLOOR RENOVATION IQAC ROOM (ZONE A & B) IN KANCHARAPARA COLLAGE , UNDER KANCHARAPARA MUNICIPALITY.

Ref. : P.W.D.Road Schedule 2015, Errata, Addenda and 2th corrigenda of Schedule of Rates for Road & Bridge Works, 2015 & P.W.D Building Schedule 2017

Sl. No	Descriptoin of Items	Unit	Quantit y	Rate /Unit	Amount (Rupees)
1	Supplying and laying true to lineand level vitrified tiles of approved brand (size not less than 600mmX600mmX10 mm thick) in floor, skirting etc. set in 20mm sand cement mortar (1:4) and 2mm thick cement slurry back side of tiles using cement @2.91Kg./sqM or using polymerised adhesive (6mm thick layer applied directly over finished artificial stone floor/Mosaic etc without any backing course) laid after application slurryusing1.75Kgof cement per sqM below mortar only, joints grouted with admixture of white cement and colouring pigment to match with colourof tiles / epoxy grout materials of approved make as directed and removal of wax coating of top surface of tiles with warm water and polishing the tiles usings of tand dry cloth upto mirror finish comple teincluding the cost of materials, labourand all other incidental charges complete true to the manufacturer's specification and direction of Engineer-in-Charge. (White cement, synthetic adhesive and grout material to be supplied by the contrr]e) I (I) With application slurry @1.75kg/ Sq.m, 20mm sand cement mortar(1:4)& 2mm thick cement slurry at back side of tiles, 0.2 kg/ Sq.m white cement for joint filling with pigment. (A) Deep Colour & White (P.No.66 T/36/I), <u>3rd CORRIGENDA & ADDENDA</u>	Sq.M	49.20	1704.00	83836.80
Total					83836.80
Add G.S.T. @ 18%					15090.62
					98927.42
Add Cess @ 1%					989.27
GRAND TOTAL					99916.70
					Say- 99917.00



SUKHENDRA KARMAKAR
L.B.S. Class-I
Licence No.- 0917P465324189468
Halisahar Municipality

Estimate No.02/KPA/24-25

ESTIMATE FOR PAINTING WITH PUTTY RENOVATION IQAC ROOM (ZONE A & B) IN KANCHARAPARA COLLAGE, UNDER KANCHARAPARA MUNICIPALITY.

Ref. : P.W.D.Road Schedule 2015, Errata, Addenda and 2th corrigenda of Schedule of Rates for Road & Bridge Works, 2015 & P.W.D Building Schedule 2017

Sl. No	Descriptoin of Items	Unit	Quantit y	Rate /Unit	Amount (Rupees)
1	Scraping and removing greasy soot from wall sorceiling of kitchen or similar smoke affected rooms and preparing the surface. (P-198, T-2)	Sq.M	156.60	11.00	1722.60
2	Rendering the Surface of walls and ceiling with White Cement base WATER PROOF wall putty of approved make & brand.(1.5 mm thick) (P-198, T-5)	Sq.M	196.00	122.00	23912.00
3	(b) Priming one coat on timber or plastered surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc. (P.200, T/1 (B))(3rd corrigendum)	Sq.M	196.00	38.00	7448.00
4	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. Including using of approved putty etc. on the surface, if necessary : (P-200, T/2 a, iv) (a) On timber or plastered surface : With super gloss (hi-gloss) - (iv) Two coats (with any shade except white) (Plaster area)	Sq.M	196.00	81.00	15876.00
5	(i) Door stopper.(Brass) (P.143, T/19/i))	Each	2.00	117.00	234.00
6	i)Hydraulic door closer of approved quality as per I.S.I.standard fitted and fixed complete. ii) Godrej Hydraulic door closer fitted and fixed complete. (a) Heavy type (P.143, T/23/ii/a))	Each	6.00	2064.00	12384.00
7	(b)Supplying 'Godrej' mortice lock chromium plated with keys 6 levers in cluding fitting & fixing complete (P.143, T/16/b))	Each	2.00	1954.00	3908.00
8	Supplying solid flush type doors of deluxe decorative (both side) quality, conforming to I:S 2202 timber frame consisting of top and bottom rail and side styles of well seasoned timber 65mm wide each and the entire frame fitted with 27.5mm wide battens places both ways in order tomade the doo rof solid core and internal lipping with teak, mahogany or rosewood approved decorative veneers using phenol formaldehyde as glue etc.complete, including fitting, fixing the shutters inpositionbut excluding the cost of hinges andother fittings in ground floor: (a) 35mm thick shutters (single leaf) (P-124, T/12.(a))	Sq.M	4.60	3955.00	18193.00
Total					83677.60
Add G.S.T. @ 18%					15061.97
98739.57					
Add Cess @ 1%					987.40
GRAND TOTAL					99726.96
Say-					99727.00


SUKHENDRA KARMAKAR
 L.B.S. Class-I
 Licence No.- 0917P465324189468
 Halisahar Municipality

Estimate No.03/KPA/24-25

ESTIMATE FOR ALUMINIUM ALLOY SECTION FOR PARTITION WALL IQAC ROOM (ZONE A & B) IN KANCHARAPARA COLLAGE , UNDER KANCHARAPARA MUNICIPALITY.

Ref. : P.W.D.Road Schedule 2015, Errata, Addenda and 2th corrigenda of Schedule of Rates for Road & Bridge Works, 2015 & P.W.D Building Schedule 2017

Sl. No	Descriptoin of Items	Unit	Quantit y	Rate /Unit	Amount (Rupees)
1	Supplying profiles of required section made of Aluminium Alloy Extrusions conforming to IS: 732-1983 and IS: 1285- 1975; Annodized (with required film thickness and specified colour / natural) matt finished conforming to IS: 1868-1983 for fabrication of composit door, sliding & casement windows, partitions, formed of basic sections of any ISI embossed / certified make and brand as per direction of Engineer - In Charge. (Payment will be made on finished length of the work).				
	j) Fixed partitions. (Unsupported length of vertical member upto 1.5 mtr. Height of both ends of vertical member restrained but panels within 0.9 sq.m.)				
	i) Top , bottom & side member. (P.No.234, T/1(i))	M	52.60	462.00	24301.20
	ii) Intermediate member.	M	63.50	480.00	30480.00
	k) Movable door shutter				
	i) Door frame. (Top & sides)	M	22.00	315.00	6930.00
	ii) Shutter :				
	Top rail.	M	3.60	318.00	1144.80
	Bottom rail.	M	3.60	487.00	1753.20
	Lock rail	M	16.80	400.00	6720.00
	Door vertical.	M	8.40	350.00	2940.00
	Glazing cleap.	M	180.60	50.00	9030.00
Total					83299.20
Add G.S.T. @ 18%					14993.86
					98293.06
Add Cess @ 1%					982.93
GRAND TOTAL					99275.99
Say-					99276.00

Sukhendra 04/09/24

SUKHENDRA KARMAKAR
L.B.S. Class-I
Licence No.- 0917P465324189468
Halisahar Municipality

Estimate No.04/KPA/24-25

ESTIMATE FOR FALSE CEILING WITH G.I GRID SUSPENSION SYSTEM & CALCIUM SILICATE BOARD FOR RENOVATION OF IQAC ROOM (ZONE A & B) IN KANCHARAPARA COLLAGE , UNDER KANCHARAPARA MUNICIPALITY.

Ref. : P.W.D.Road Schedule 2015, Errata, Addenda and 2th corrigenda of Schedule of Rates for Road & Bridge Works, 2015 & P.W.D Building Schedule 2017

Sl. No	Descriptoin of Items	Unit	Quantit y	Rate /Unit	Amount (Rupees)
1	Providing and fixing of false ceiling with powder coated exposed G.I. grid suspension system (E-Grid T 2430/1510 or equivalent load carrying capacity with mid span deflection not exceeding 1/360 span with hanger spacing of 1200mm c/c) consisting of Main Runner 3600 mm long, Cross Tee 1200 mm / 600 mm long and Wall Angle. The Wall Angle shall be fixed on PVC Dash Fasteners on the perimeter of the wall by steel screws with distance 300mm c/c. The Main Runners to be placed @ 1200 mm. The Cross Tee 1200mm will be inserted in the pre-cut slots of Main Runner at a regular interval of 600 mm to form a modular grid of 1200mm X 600mm. Additional Cross Tees of 600 mm shall be placed perpendicular to the Cross Tee 1200 mm long to finally form a grid of 600 mm X 600 mm. Grid of module size 600 mm X 600 mm shall be supported by 6 mm dia G.I. wire from purlins / soffit. 4 mm thick High Pressure Steam Cured Non Asbestos pearl designer Fibre Cement Standard Ceiling Board (Density > 1500Kg/m ³) of size 595 mm X 595 mm, conforming IS 14862 & Type A Category IV of ISO 8336, tested as per AS-1530 part 3 & BS-476 Part 4,5,6,7 & 8, should be placed in the Grid module to form a False Ceiling. All complete as per the drawing & directions of Engineer-in- a) False Ceiling (with 4mm thick Pearl Designer Fibre Cement Board and E-Grid T-2430/1510). (P.No.160, T/04/a),	Sq.M	72.10	705.00	50830.50
2	(e)Supplying, fitting & fixing Eco-friendly,Water Resistance and Incombustable Calcium Silicate board / tiles (Density> 900KgperCu.m.) of approved design and brand finished with calcium silicate jointing compound to form a joint less false ceiling all complete as per drawing & direction of Engineer - in- Charge.False ceiling with (ii) 8mm thick square edged Calcium Silicate Board (P.No.171 T/36/e/ii),	Sq.M	72.10	457.00	32949.70
Total					83780.20
Add G.S.T. @ 18%					15080.44
Add Cess @ 1%					988.61
GRAND TOTAL					99849.24
Say-					99849.00

Sukhendra 04/09/24

SUKHENDRA KARMAKAR
L.B.S. Class-I
Licence No.- 0917P465324189468
Halisahar Municipality

Estimate No.05/KPA/24-25

ESTIMATE FOR PARTITION WALL WITH ACP SHEET FOR RENOVATION IQAC ROOM (ZONE A) IN KANCHARAPARA COLLAGE , UNDER KANCHARAPARA MUNICIPALITY.

Ref. : P.W.D.Road Schedule 2015, Errata, Addenda and 2th corrigenda of Schedule of Rates for Road & Bridge Works, 2015 & P.W.D Building Schedule 2017

Sl. No	Descriptoin of Items	Unit	Quantit y	Rate /Unit	Amount (Rupees)
9	Providing and fixing exterior quality Aluminium Composite Panel (ACP) wall cladding on existing Al. /MS frame work with GI brackets, ACP fixed on the existing frame work by folding the edges of ACP panel (Engraving the rear surface of ACP sheet) with CP angles, cleats and strainless Steel screws forming groves at the periphery of ACP panel. Such grooves filled with foam and silicon sealant etc. complete with all materials (but including the cost of silicon sealant), labour, scaffolding and all other incidental charges complete in all respect as per specification and direction of Engineer-in-charge. (Mode of payment is on finished surface area of ACP) (b) 4mm thick (0.50mm Al.+3.0mm LDPE +0.50mm Al. PVDF coating) (P-250, T/27,(b)	Sq.M	29.10	2878.00	83749.80
Total					83749.80
Add G.S.T. @ 18%					15074.96
Add Cess @ 1%					988.25
GRAND TOTAL					99813.01
Say-					99813.00

 04/09/24
SUKHENDRA KARMAKAR
L.B.S. Class-I
Licence No.- 0917P465324189468
Halisahar Municipality

Estimate No.06/KPA/24-25**ESTIMATE FOR PARTITION WALL WITH ACP SHEET FOR RENOVATION IQAC ROOM (ZONE B) & DOORS FRAMES IN KANCHARAPARA COLLAGE , UNDER KANCHARAPARA MUNICIPALITY.**

Ref. : P.W.D.Road Schedule 2015, Errata, Addenda and 2th corrigenda of Schedule of Rates for Road & Bridge Works, 2015 & P.W.D Building Schedule 2017

Sl. No	Descriptoin of Items	Unit	Quantit y	Rate /Unit	Amount (Rupees)
1	Providing and fixing exterior quality Aluminium Composite Panel (ACP) wall cladding on existing Al. /MS frame work with GI brackets, ACP fixed on the existing frame work by folding the edges of ACP panel (Engraving the rear surface of ACP sheet) with CP angles, cleats and stainless Steel screws forming grooves at the periphery of ACP panel. Such grooves filled with foam and silicon sealant etc. complete with all materials (but including the cost of silicon sealant), labour, scaffolding and all other incidental charges complete in all respect as per specification and direction of Engineer-in-charge. (Mode of payment is on finished surface area of ACP) (b) 4mm thick (0.50mm Al.+3.0mm LDPE +0.50mm Al. PVDF coating) (P-250, T/27,(b))	Sq.M	23.80	2878.00	68496.40
2	Wood work in door and window frame fitted and fixed in position complete including a protective coat of painting at the contact surface of the frame exluding cost of concrete, Iron Butt Hinges and M.S clamps.(The quantum should be correted upto three decimals). (d) Sal : Local. (P.no. 114, T/1/f)	Cu.m	0.19	77671.00	14446.81
Total					82943.21
Add G.S.T. @ 18%					14929.78
Add Cess @ 1%					978.73
GRAND TOTAL					98851.71
Say-					98852.00

Sukhendra Karmakar 04/09/24
SUKHENDRA KARMAKAR
L.B.S. Class-1
Licence No.-0917P465324189468
Halisahar Municipality

Estimate No.07/KPA/24-25

ESTIMATE FOR ELECTRIC LED LIGHT & WIRING AT IQAC ROOM (ZONE A & B) IN KANCHARAPARA COLLAGE , UNDER KANCHARAPARA MUNICIPALITY.

Ref. : P.W.D.Road Schedule 2015, Errata, Addenda and 2th corrigenda of Schedule of Rates for Road & Bridge Works, 2015 & P.W.D Building Schedule 2017

Sl. No	Descriptoin of Items	Unit	Quantit y	Rate /Unit	Amount (Rupees)
1	Providing and fixing exterior quality Philips 22 W Neutral White LED Downlighter with ELECTRICAL WORKS- fitting & fixing switch board , wiring , wall cutting including finishing. MARKET RATE	Each	28.00	1550.00	43400.00
Total					43400.00
Add G.S.T. @ 18%					7812.00
Add Cess @ 1%					512.12
GRAND TOTAL					51724.12
Say-					51724.00

Sukhendra Karmakar 04/09/24
SUKHENDRA KARMAKAR
L.B.S. Class-1
Licence No.-0917P465324189468
Halisahar Municipality

Estimate No. N01/KPA/24-25

ESTIMATE FOR TILES WORK & PUTTY WORK AT NSS ROOM IN KANCHARAPARA COLLAGE , UNDER KANCHARAPARA MUNICIPALITY.

Ref. : P.W.D.Road Schedule 2015, Errata, Addenda and 2th corrigenda of Schedule of Rates for Road & Bridge Works, 2015 & P.W.D Building Schedule 2017

Sl. No	Description of Items	Unit	Quantity	Rate /Unit	Amount (Rupees)
1	Scraping and removing greasy soot from wall soor ceiling of kitchen or similar smoke affected rooms and preparing the surface. (P-198, T-2)	Sq.M	128.80	11.00	1416.80
2	Rendering the Surface of walls and ceiling with White Cement base WATER PROOF wall putty of approved make & brand.(1.5 mm thick) (P-198, T-5)	Sq.M	128.80	122.00	15713.60
3	Supplying and laying true to line and level vitrified tiles of approved brand (size not less than 600mmX600mmX10 mm thick) in floor, skirting etc. set in 20mm sand cement mortar (1:4) and 2mm thick cement slurry back side of tiles using cement @2.91Kg./sqM or using polymerised adhesive (6mm thick layer applied directly over finished artificial stone floor/Mosaic etc without any backing course) laid after application slurry using 1.75Kg of cement per sqM below mortar only, joints grouted with admixture of white cement and colouring pigment to match with colour of tiles / epoxy grout materials of approved make as directed and removal of wax coating of top surface of tiles with warm water and polishing the tiles using of tanned dry cloth upto mirror finish complete including the cost of materials, labour and all other incidental charges complete true to the manufacturer's specification and direction of Engineer-in-Charge. (White cement, synthetic adhesive and grout material to be supplied by the contractor) I (I) With application slurry @1.75kg/ Sq.m, 20mm sand cement mortar(1:4)& 2mm thick cement slurry at back side of tiles, 0.2 kg/ Sq.m white cement for joint filling with pigment. (A) Deep Colour & White (P.No.66 T/36/I), 3rd CORRIGENDA & ADDENDA	Sq.M	38.85	1704.00	66200.40
Total					83330.80
Add G.S.T. @ 18%					14999.54
98330.34					
Add Cess @ 1%					983.30
GRAND TOTAL					99313.65
Say-					99314.00


SUKHENDRA KARMAKAR
 L.B.S. Class-I
 Licence No.- 0917P465324189468
 Halisahar Municipality

ESTIMATE FOR SUPPLY , FITTING & FIXING WARDROBE IQAC ROOM (ZONE A & B) IN KANCHARAPARA COLLAGE , UNDER KANCHARAPARA MUNICIPALITY.

Ref. : P.W.D.Road Schedule 2015, Errata, Addenda and 2th corrigenda of Schedule of Rates for Road & Bridge Works, 2015 & P.W.D Building Schedule 2017

Sl. No	Descriptoin of Items	Unit	Quantit y	Rate /Unit	Amount (Rupees)
1	Supplying fitting, fixing decorative lamination conforming to IS:2046:1995 as per approved make, brand, finishand thickness with fitting, fixing the same on Particle / MDF / Ply Boards with recommended / approved adhesive with proper clipping the sides for better attachment as per direction of Engineer-in charge.The rate includes the costof labour, adhesive and all incidental charges thereof. In ground floor. Glossy/Matt/Suede excluding surface texture or metallic lustre.(i) Thickness of laminate 1.5mm Page -179, T- 14/i	Sq.M	10.47	802.00	8396.94
2	Supplying, fitting and fixing boiling water proof block board conforming to IS:1659-1990 conforming to IS:848-1974 of approved make and brand , fitted and fixed as per design as per direction of Engineer-in-charge.[Excluding the cost of supporting frame work and teak wood batten/Lipping]. In Ground Floor (ii) 19mm Page -173, T- 4/ii	Sq.M	31.56	1827.00	57660.12
3	Supplying , fitting and fixing Godrej ultra vertibold brass rim lock. Page -147, T- 36	Each	4.00	1678.00	6712.00
Total					72769.06
Add G.S.T. @ 18%					13098.43
					85867.49
Add Cess @ 1%					858.67
GRAND TOTAL					86726.17
Say-					86726.00

Sukhendra Karmakar 04/09/24

SUKHENDRA KARMAKAR
L.B.S. Class-1
Licence No.- 0917P465324189468
Halisahar Municipality

Estimate No. N02/KPA/24-25

ESTIMATE FOR PAINTING WITH PUTTY , TILES , NSS ROOM IN KANCHARAPARA COLLAGE , UNDER KANCHARAPARA MUNICIPALITY.

Ref. : P.W.D.Road Schedule 2015, Errata, Addenda and 2th corrigenda of Schedule of Rates for Road & Bridge Works, 2015 & P.W.D Building Schedule 2017

Sl. No	Descriptoin of Items	Unit	Quantit y	Rate /Unit	Amount (Rupees)
1	(b) Priming one coat on timber or plastered surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc. (P.200, T/1 (B))(3rd corrigendum) same as T/12	Sq.M	128.80	38.00	4894.40
2	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. Including using of approved putty etc. on the surface, if necessary : (P-200, T/2 a, iv) (a) On timber or plastered surface : With super gloss (hi-gloss) - (iv) Two coats (with any shade except white) (Plaster area) Same as T/19 (b)	Sq.M	128.80	81.00	10432.80
3	(i) Door stopper.(Brass) (P.143, T/19/i)	Each	1.00	117.00	117.00
4	i)Hydraulic door closer of approved quality as per I.S.I.standard fitted and fixed complete. ii) Godrej Hydraulic door closer fitted and fixed complete. (a) Heavy type (P.143, T/23/ii/a)	Each	1.00	2064.00	2064.00
5	(b)Supplying 'Godrej' mortice lock chromium plated with keys 6 levers in cluding fitting & fixing complete (P.143, T/16/b)	Each	1.00	1954.00	1954.00
6	Supplying solid flush type doors of deluxe decorative (both side) quality, conforming to I:S 2202 timber frame consisting of top and bottom rail and side styles of well seasoned timber 65mm wide each and the entire frame fitted with 27.5mm wide battens places both ways in order tomade the doo rof solid core and internal lipping with teak, mahogany or rosewood approved decorative veneers using phenol formaldehyde as glue etc.complete, including fitting, fixing the shutters inpositionbut excluding the cost of hinges andother fittings in ground floor: (a) 35mm thick shutters (single leaf) (P-124, T/12,(a)	Sq.M	4.04	3955.00	15978.20

Karmakar 04/09/24

SUKHENDRA KARMAKAR
L.B.S. Class-1
Licence No.- 0917P465324189468
Halisahar Municipality


7	Wood work in door and window frame fitted and fixed in position complete including a protective coat of painting at the contact surface of the frame exluding cost of concrete, Iron Butt Hinges and M.S clamps.(The quantum should be correted upto three decimals). (d) Sal : Local. (P.no. 114, T/1/f)	Cu.m	0.10	77671.00	7767.10
8	Providing and fixing exterior quality Philips 22 W Neutral White LED Downlighter with ELECTRICAL WORKS- fitting & fixing switch board , weiring , wall cutting inchluding finishing. MARKET RATE	Each	15.00	1550.00	23250.00
Total					66457.50
Add G.S.T. @ 18%					11962.35
					78419.85
Add Cess @ 1%					784.20
GRAND TOTAL					79204.05
Say-					79204.00

 04/09/24
SUKHENDRA KARMAKAR
L.B.S. Class-1
Licence No.- 0917P465324189468
Halisahar Municipality

Estimate No. B01/KPA/24-25**ESTIMATE FOR PUTTY, FALSE CEILING & TILES WORK AT IQCE BATHROOM (ZONE A & B) IN KANCHARAPARA COLLAGE , UNDER KANCHARAPARA MUNICIPALITY.**

Ref. : P.W.D.Road Schedule 2015, Errata, Addenda and 2th corrigenda of Schedule of Rates for Road & Bridge Works, 2015 & P.W.D Building Schedule 2017

Sl. No	Descriptoin of Items	Unit	Quantit y	Rate /Unit	Amount (Rupees)
1	Scraping and removing greasy soot from wall sorceiling of kitchen or similar smoke affected rooms and preparing the surface. (P-198, T-2)	Sq.M	38.60	11.00	424.60
2	Rendering the Surface of walls and ceiling with White Cement base WATER PROOF wall putty of approved make & brand.(1.5 mm thick) (P-198, T-5)	Sq.M	24.60	122.00	3001.20
3	Supplying and laying true to lineand level vitrified tiles of approved brand (size not less than 600mmX600mmX10 mm thick) in floor, skirting etc. set in 20mm sand cement mortar (1:4) and 2mm thick cement slurry back side of tiles using cement @2.91Kg./sqM or using polymerised adhesive (6mm thick layer applied directly over finished artificial stone floor/Mosaic etc without any backing course) laid after application slurryusing1.75Kgof cement per sqM below mortar only, joints grouted with admixture of white cement and colouring pigment to match with colourof tiles / epoxy grout materials of approved make as directed and removal of wax coating of top surface of tiles with warm water and polishing the tiles usings of tand dry cloth upto mirror finish comple teincluding the cost of materials, labourand all other incidental charges complete true to the manufacturer's specification and direction of Engineer-in-Charge. (White cement, synthetic adhesive and grout material to be supplied by the contrr]e) I (I) With application slurry @1.75kg/ Sq.m, 20mm sand cement mortar(1:4)& 2mm thick cement slurry at back side of tiles, 0.2 kg/ Sq.m white cement for joint filling with pigment. (A) Deep Colour & White (P.No.66 T/36/I), <u>3rd CORRIGENDA & ADDENDA</u>	Sq.M	28.68	1704.00	48870.72



SUKHENDRA KARMAKAR
L.B.S. Class-1
Licence No.- 0917P465324189468
Halisahar Municipality

4	<p>Providing and fixing of false ceiling with powder coated exposed G.I. grid suspension system (E-Grid T 2430/1510 or equivalent load carrying capacity with mid span deflection not exceeding 1/360 span with hanger spacing of 1200mm c/c) consisting of Main Runner 3600 mm long, Cross Tee 1200 mm / 600 mm long and Wall Angle. The Wall Angle shall be fixed on PVC Dash Fasteners on the perimeter of the wall by steel screws with distance 300mm c/c. The Main Runners to be placed @ 1200 mm. The Cross Tee 1200mm will be inserted in the pre-cut slots of Main Runner at a regular interval of 600 mm to form a modular grid of 1200mm X 600mm. Additional Cross Tees of 600 mm shall be placed perpendicular to the Cross Tee 1200 mm long to finally form a grid of 600 mm X 600 mm. Grid of module size 600 mm X 600 mm shall be supported by 6 mm dia G.I. wire from purlins / soffit. 4 mm thick High Pressure Steam Cured Non Asbestos pearl designer Fibre Cement Standard Ceiling Board (Density > 1500Kg/m³) of size 595 mm X 595 mm, conforming IS 14862 & Type A Category IV of ISO 8336, tested as per AS-1530 part 3 & BS-476 Part 4,5,6,7 & 8, should be placed in the Grid module to form a False Ceiling. All complete as per the drawing & directions of Engineer-in-charge.</p> <p>a) False Ceiling (with 4mm thick Pearl Designer Fibre Cement Board and E-Grid T-2430/1510). (P.No.160, T/04/a),</p>	Sq.M	12.48	705.00	8798.40
5	<p>(e)Supplying, fitting & fixing Eco-friendly,Water Resistance and Incombustable Calcium Silicate board / tiles (Density> 900KgperCu.m.) of approved design and brand finished with calcium silicate jointing compound to form a joint less false ceiling all complete as per drawing & direction of Engineer - in- Charge.False ceiling with</p> <p>(ii) 8mm thick square edged Calcium Silicate Board (P.No.171 T/36/e/ii),</p>	Sq.M	12.48	457.00	5703.36

Sukhendra Karmakar
04/09/24

SUKHENDRA KARMAKAR
L.B.S. Class-I
Licence No.-0917P465324189468
Halisahar Municipality

Estimate No. B02/KPA/24-25

ESTIMATE FOR PAINTING & SANITARY FITTINGS AT IQCE BATHROOM (ZONE A & B) IN KANCHARAPARA COLLAGE , UNDER KANCHARAPARA MUNICIPALITY.

Ref. : P.W.D.Road Schedule 2015, Errata, Addenda and 2th corrigenda of Schedule of Rates for Road & Bridge Works, 2015 & P.W.D Building Schedule 2017

Sl. No	Descriptoin of Items	Unit	Quantit y	Rate /Unit	Amount (Rupees)
1	Brick work with 1st class bricks in cement mortar (1:6) (P.No.30, T/22 b) , 3rd corrigenda, (a) In foundation and Plinth.	Cu.M	4.56	5413.00	24683.28
2	(b) Priming one coat on timber or plastered surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc. (P.200, T/1 (B))(3rd corrigendum)	Sq.M	12.15	38.00	461.70
3	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. Including using of approved putty etc. on the surface, if necessary : (P-200, T/2 a, iv) (a) On timber or plastered surface : With super gloss (hi-gloss) - (iv) Two coats (with any shade except white) (Plaster area) Same as T/19 (b)	Sq.M	12.15	81.00	984.15
4	(i) Door stopper.(Brass) (P.143, T/19/i))	Each	1.00	117.00	117.00
5	(b)Supplying 'Godrej' mortice lock chromium plated with keys 6 levers in cluding fitting & fixing complete (P.143, T/16/b))	Each	1.00	1954.00	1954.00
6	(b)Openable steel windows as per IS sizes with side hung shutters and horizotal glazing bars. [The extra rate admissible for the openable portion only] (P.107, T/20/b))	Sq.M	0.90	1954.00	1758.60
7	BATHROOM SET- (WALL MIXER 3 IN 1 + 5 FLOW + 5FLOW SHOWER + HAND SHOWER + BASIN MIXER + ANGLE COCK) (HEAVY DUTY) BATHROOM SET (WATER TAP) WASH BASIN TAP Mixer Faucet (Wall Mount Installation Type) MARKET RATE	Each	1.00	9650.00	9650.00
8	HAVELLS FHVSUSTWHT10 250 mm Exhaust Fan (White) MARKET RATE	Each	1.00	3360.00	3360.00
9	Water Closet With Soft Close Toilet Seat Premium Grade Ceramic's One Piece Western Commode (WHITE) MARKET RATE	Each	1.00	11570.00	11570.00
10	Ceramic Altis 23 Inch x 17 Inch for Bathroom / Toilet / Washroom / Dining Pedestal Basin (White) MARKET RATE	Each	1.00	9540.00	9540.00

Sukhendra Karmakar
04/09/24

SUKHENDRA KARMAKAR
L.B.S. Class-I
Licence No.- 0917P465324189468
Halisahar Municipality

11	Large 24"x15"x13" Standard Commode Urinal (White) MARKET RATE	Each	1.00	7100.00	7100.00
12	Jet Spray Chrome with 8mm Dia, 1 Meter Long Flexible Tube & Wall Hook Health Faucet (Wall Mount Installation Type) MARKET RATE	Each	1.00	2650.00	2650.00
13	Providing and fixing exterior quality Philips 22 W Neutral White LED Downlighter with ELECTRICAL WORKS- fitting & fixing switch board , weiring , wall cutting including finishing MARKET RATE	1 JOB	1.00	9580.00	9580.00
Total					83408.73
Add G.S.T. @ 18%					15013.57
98422.30					
Add Cess @ 1%					984.22
GRAND TOTAL					99406.52
Say-					99407.00

Sukhendra - 04/09/24
SUKHENDRA KARMAKAR
L.B.S. Class-1
Licence No.-0917P465324189468
Halisahar Municipality

Estimate No. D01/KPA/24-25

ESTIMATE FOR PAINTING WITH PUTTY , TILES DOCTOR ROOM IN KANCHARAPARA COLLAGE , UNDER KANCHARAPARA MUNICIPALITY.

Ref. : P.W.D.Road Schedule 2015, Errata, Addenda and 2th corrigenda of Schedule of Rates for Road & Bridge Works, 2015 & P.W.D Building Schedule 2017

Sl. No	Descriptoin of Items	Unit	Quantit y	Rate /Unit	Amount (Rupees)
1	Scraping and removing greasy sòot from wall sorceiling of kitchen or similar smoke affected rooms and preparing the surface. (P-198, T-2)	Sq.M	49.54	11.00	544.94
2	Rendering the Surface of walls and ceiling with White Cement base WATER PROOF wall putty of approved make & brand.(1.5 mm thick) (P-198, T-5)	Sq.M	49.54	122.00	6043.88
3	Supplying and laying true to lineand level vitrified tiles of approved brand (size not less than 600mmX600mmX10 mm thick) in floor, skirting etc. set in 20mm sand cement mortar (1:4) and 2mm thick cement slurry back side of tiles using cement @2.91Kg./sqM or using polymerised adhesive (6mm thick layer applied directly over finished artificial stone floor/Mosaic etc without any backing course) laid after application slurryusing1.75Kgo f cement per sqM below mortar only, joints grouted with admixture of white cement and colouring pigment to match with colour of tiles / epoxy grout materials of approved make as directed and removal of wax coating of top surface of tiles with warm water and polishing the tiles usings of tand dry cloth upto mirror finish comple teincluding the cost of materials, labourand all other incidental charges complete true to the manufacturer's specification and direction of Engineer-in-Charge. (White cement, synthetic adhesive and grout material to be supplied by the contrrle) T (I) With application slurry @1.75kg/ Sq.m, 20mm sand cement mortar(1:4)& 2mm thick cement slurry at back side of tiles, 0.2 kg/ Sq.m white cement for joint filling with pigment. (A) Deep Colour & White (P.No.66 T/36/I), <u>3rd CORRIGENDA & ADDENDA</u>	Sq.M	9.92	1704.00	16903.68
4	(b) Priming one coat on timber or plastered surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc. (P.200, T/1 (B))(3rd corrigendum) same as T/12 = 49.54 Sq.M	Sq.M	49.54	38.00	1882.52

Sukhendra Karmakar, 04/09/24

SUKHENDRA KARMAKAR
L.B.S. Class-1
Licence No.- 0917P465324189468
Halisahar Municipality

5	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. Including using of approved putty etc. on the surface, if necessary : (P-200, T/2 a, iv) (a) On timber or plastered surface : With super gloss (hi-gloss) - (iv) Two coats (with any shade except white) (Plaster area) Same as T/19 (b) = 49.54 Sq.M	Sq.M	49.54	81.00	4012.74
Total					29387.76
Add G.S.T. @ 18%					5289.80
Add Cess @ 1%					346.78
GRAND TOTAL					35024.33
Say-					35024.00

Sukhendra Karmakar 04/09/24

SUKHENDRA KARMAKAR
L.B.S. Class-1
Licence No.-0917P465324189468
Halisahar Municipality

a/

ESTIMATE FOR SUPPLY , FITTING & FIXING WARDROBE IN IQAC ROOM (ZONE A & B) IN KANCHARAPARA COLLAGE , UNDER KANCHARAPARA MUNICIPALITY.

Ref. : P.W.D.Road Schedule 2015, Errata, Addenda and 2th corrigenda of Schedule of Rates for Road & Bridge Works, 2015 & P.W.D Building Schedule 2017

Sl. No	Descriptoin of Items	Unit	Quantit y	Rate /Unit	Amount (Rupees)
1	Supplying fitting, fixing decorative lamination conforming to IS:2046:1995 as per approved make, brand, finished thickness with fitting, fixing the same on Particle / MDF Ply Boards with recommended / approved adhesive with proper clipping the sides for better attachment as per direction of Engineer-in charge.The rate includes the cost of labour, adhesive and all incidental charges thereof. In ground floor. Glossy/Matt/Suede excluding surface texture or metallic lustre.(i) Thickness of laminate 1.5mm Page -179, T- 14/i	Sq.M	10.47	802.00	8396.94
2	Supplying, fitting and fixing boiling water proof block board conforming to IS:1659-1990 conforming to IS:848-1974 of approved make and brand , fitted and fixed as per design as per direction of Engineer-in-charge.[Excluding the cost of supporting frame work and teak wood batten/Lipping]. In Ground Floor (ii) 19mm Page -173, T- 4/ii	Sq.M	31.56	1827.00	57660.12
3	Supplying , fitting and fixing Godrej ultra vertibold brass rim lock. Page -147, T- 36	Each	4.00	1678.00	6712.00
Total					72769.06
Add G.S.T. @ 18%					13098.43
Add Cess @ 1%					85867.49
GRAND TOTAL					858.67
Say-					86726.17
Say-					86726.00

Sukhendra Karmakar, 04/09/24

SUKHENDRA KARMAKAR
L.B.S. Class-I
Licence No.- 0917P465324189468
Halisahar Municipality